




| DR # | DOOR SIZE | THICK | DOOR/FRAME | REMARKS |
|------|-------------------|--------|------------|---------------------|
| A | (2) 3'-0" x 7'-0" | 1 3/4" | D1 | F1 INSULATING GLASS |
| B | (2) 3'-0" x 7'-0" | 1 3/4" | D1 | F1 INSULATING GLASS |

- NOTES:
- ALL DOOR HARDWARE TO BE SPECIFIED & PROVIDED BY CONTRACTOR
 - ALL EXIT HARDWARE SHALL NOT REQUIRE TIGHT GRASPING, PINCHING, OR TWISTING OF THE WRIST. MOUNT HARDWARE BETWEEN 34"-48" (ANSI A117.1-404.2.6)
 - PROVIDE A KNOX BRAND FIRE DEPARTMENT KEY BOX AS SPECIFIED BY THE FIRE MARSHAL
 - THE MAIN EXIT IS ALLOWED TO HAVE A KEYED LOCK PROVIDED THAT THE LOCKING DEVICE IS READILY DISTINGUISHABLE AS LOCKED AND A SIGN WITH "I" CONTRASTING LETTERS IS POSTED ON THE EGRESS SIDE STATING: "THIS DOOR TO REMAIN UNLOCKED WHEN BUILDING IS OCCUPIED." (IBC 1008.1.9.3)



3 WINDOW TYPE
SCALE: 1/4" = 1'-0"

4 FRAME TYPE
SCALE: 1/4" = 1'-0"

5 DOOR TYPE
SCALE: 1/4" = 1'-0"

ANODIZED ALUMINUM INSULATING GLASS WITH LOW-E COATING

ANODIZED ALUMINUM INSULATING GLASS WITH LOW-E COATING

ANODIZED ALUMINUM INSULATING GLASS WITH LOW-E COATING

ANODIZED ALUMINUM INSULATING GLASS WITH LOW-E COATING

ANODIZED ALUMINUM INSULATING GLASS WITH LOW-E COATING

ANODIZED ALUMINUM INSULATING GLASS WITH LOW-E COATING

ANODIZED ALUMINUM INSULATING GLASS WITH LOW-E COATING

ANODIZED ALUMINUM INSULATING GLASS WITH LOW-E COATING

ANODIZED ALUMINUM INSULATING GLASS WITH LOW-E COATING

ANODIZED ALUMINUM INSULATING GLASS WITH LOW-E COATING

ANODIZED ALUMINUM INSULATING GLASS WITH LOW-E COATING

ANODIZED ALUMINUM INSULATING GLASS WITH LOW-E COATING

ANODIZED ALUMINUM INSULATING GLASS WITH LOW-E COATING

ANODIZED ALUMINUM INSULATING GLASS WITH LOW-E COATING

ANODIZED ALUMINUM INSULATING GLASS WITH LOW-E COATING

ANODIZED ALUMINUM INSULATING GLASS WITH LOW-E COATING

ANODIZED ALUMINUM INSULATING GLASS WITH LOW-E COATING

ANODIZED ALUMINUM INSULATING GLASS WITH LOW-E COATING

ANODIZED ALUMINUM INSULATING GLASS WITH LOW-E COATING

ANODIZED ALUMINUM INSULATING GLASS WITH LOW-E COATING

ANODIZED ALUMINUM INSULATING GLASS WITH LOW-E COATING

ANODIZED ALUMINUM INSULATING GLASS WITH LOW-E COATING

ANODIZED ALUMINUM INSULATING GLASS WITH LOW-E COATING

ANODIZED ALUMINUM INSULATING GLASS WITH LOW-E COATING

ANODIZED ALUMINUM INSULATING GLASS WITH LOW-E COATING

ANODIZED ALUMINUM INSULATING GLASS WITH LOW-E COATING

ANODIZED ALUMINUM INSULATING GLASS WITH LOW-E COATING

ANODIZED ALUMINUM INSULATING GLASS WITH LOW-E COATING

ANODIZED ALUMINUM INSULATING GLASS WITH LOW-E COATING

ANODIZED ALUMINUM INSULATING GLASS WITH LOW-E COATING

ANODIZED ALUMINUM INSULATING GLASS WITH LOW-E COATING

ANODIZED ALUMINUM INSULATING GLASS WITH LOW-E COATING

ANODIZED ALUMINUM INSULATING GLASS WITH LOW-E COATING

ANODIZED ALUMINUM INSULATING GLASS WITH LOW-E COATING

ANODIZED ALUMINUM INSULATING GLASS WITH LOW-E COATING

ANODIZED ALUMINUM INSULATING GLASS WITH LOW-E COATING

ANODIZED ALUMINUM INSULATING GLASS WITH LOW-E COATING


ANODIZED ALUMINUM INSULATING GLASS WITH LOW-E COATING

2 SOUTH ELEVATION
SCALE: 1/8" = 1'-0"


NOTE TO CONTRACTOR:
VERIFY ALL EXISTING CONDITIONS PRIOR TO CONSTRUCTION.

NOTE TO ALL DESIGN/BUILD CONTRACTORS AND THEIR SUB-CONTRACTORS:
THE DESIGN/BUILD CONTRACTOR IS RESPONSIBLE FOR REVIEWING ALL MECHANICAL, ELECTRICAL, PLUMBING, FIRE SPRINKLER, OR ANY OTHER DESIGN/BUILD SUB-CONTRACTOR'S DOCUMENTS AS PERTAINING TO THE WORK FOR THIS PROJECT. IT IS THE DESIGN/BUILD SUB-CONTRACTOR'S RESPONSIBILITY TO NOTIFY THE DESIGN/BUILD CONTRACTOR OF ANY CONFLICTS WITH THE ARCHITECTURAL AND STRUCTURAL DOCUMENTS DUE TO SIZES, LOCATIONS, QUANTITIES, ROUGH-IN DIMENSIONS AND CODE INTERPRETATIONS. THE DESIGN/BUILD CONTRACTOR IS RESPONSIBLE FOR NOTIFYING THE ARCHITECT IMMEDIATELY OF ANY ARCHITECTURAL REVISIONS REQUIRED DUE TO THE COORDINATION OF EACH DESIGN/BUILD SUB-CONTRACTOR'S DOCUMENTS.


- GENERAL NOTES:
- EXIT SIGNAGE. PROVIDE EMERGENCY BACK-UP POWER
 - EMERGENCY LIGHTING. PROVIDE EMERGENCY BACK-UP POWER AND (1) FOOT CANDLE AT THE WALKING SURFACE.
 - PLAN KEY:
--- = TO BE DEMOLISHED
--- = EXISTING TO REMAIN
--- = NEW CONSTRUCTION



2 MAIN FLOOR PLAN
SCALE: 1/8" = 1'-0"



6 INTEGRAL CONCRETE CURB
SCALE: 1" = 1'-0"



7 ACCESSIBLE CURB CUT
SCALE: 1/4" = 1'-0"

- ACCESSIBLE CURB CUT NOTES:
- CURB RAMP TO COMPLY WITH ICC/ANSI A117.1 SECTION 406 AND 705
 - CURB RAMP AND ACCESSIBLE AISLE SHALL BE DESIGNED TO PREVENT WATER FROM PONDING
 - CROSS SLOPES ON CURB RAMP NOT TO EXCEED 1:48

COMMERCIAL PLAN REVIEW
FOR CODE COMPLIANCE

GENERAL INFORMATION
A. PROJECT NAME: (Project Name)
B. PROJECT LOCATION: Address Line #2
Address Line #2


- APPLICABLE CODES:
- A. BLOOMINGTON ZONING ORDINANCE - Current Edition
 - B. MINNESOTA STATE BUILDING CODE (MSBC) - 2015 Edition
 - C. INT'L BUILDING CODE (W/ AMENDMENTS) - 2012 Edition
 - D. INT'L FIRE CODE (W/ AMENDMENTS) - 2012 Edition
 - E. INT'L MECHANICAL CODE (W/ AMENDMENTS) - 2012 Edition
 - F. MINNESOTA PLUMBING CODE - 2015 Edition
 - G. NATIONAL ELECTRICAL CODE (NEC) - 2017 Edition
 - H. MINNESOTA STATE ENERGY CODE - 2015 Edition
 - J. MINNESOTA STATE ACCESSIBILITY CODE - 2015 Edition
 - K. MINNESOTA CONSERVATION CODE /EX BLDGS - 2015 Edition

BUILDING CLASSIFICATION
A. OCCUPANCY GROUPS/ TYPE OF CONST (IBC Chpt 3 & IBC Chpt 6)
1. Potential Occupancy Groups: A, B, E, M, S
- Type of Construction - II-B
- Area - 22,055 s.f. (Main Floor)
2. Occupancy and Type Of Construction Are Unchanged.

AUTOMATIC SPRINKLER REQUIREMENTS
A. AN EXISTING NFPA 13 AUTOMATIC SPRINKLER SYSTEM IS PROVIDED THROUGHOUT THE BUILDING (IBC 903.3.1.1)

MEANS OF EGRESS
A. DESIGN OCCUPANT LOAD (IBC Table 1004.1.2)
1. Occupancy of Existing Occupied Spaces Are Unchanged
2. Occupancy of Vacancies To Be Determined With Tenant Build-out
B. EXITS
1. Exiting Patterns Of Existing Occupied Spaces Are Unchanged
2. Exiting of Vacancies To Be Determined With Tenant Build-out
6. Doors
- Swing (IBC 1008.1.2)
- Side Hinged Swinging Out At Occupant Load Of 50 Or More
- Landings (IBC 1008.1.6)
- Width Not Less Than Width of Door
- Length in Direction of Travel Not Less Than 44"
- Thresholds (IBC 1008.1.7)
- Max Height = 1/2" - 1:2 Beveled Edge If 1/4"-1/2"
- Door Arrangement (IBC 1008.1.8) 48" + Door Width Apart
- Lock or Latch (IBC 1008.1.9)
- Operable From Inside Without Use of Knowledge or Keys.
- Panic/ Fire Exit Hardware (IBC 1008.1.10)
- Not Required At Exit/Exit Access Doors

OTHER
A. ACCESSIBILITY (MN State Accessibility Code)
1. Building is Accessible
B. GUARDS (IBC 1013)
1. 42" High Minimum Guards Shall Be Installed Where A Change in Levels Drops 30" Or More.
C. SAFETY GLAZING (IBC 2406)
1. Safety Glazing Shall Be Installed in Hazardous Locations As Specified in IBC 2406.4
D. FIRE ALARM AND DETECTION SYSTEMS
1. Manual Fire Alarms Not Required (IBC 907.2)
2. Provide audible and visible alarm notification devices (IBC 907.5, NFPA 72)



LAMPERT ARCHITECTS
420 Summit Avenue
St. Paul, MN 55102
Phone: 763.755.1211 Fax: 763.757.2849
lampert@lampert-arch.com

ARCHITECT CERTIFICATION:
I HEREBY CERTIFY THAT THIS PLAN, SPECIFICATION OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED ARCHITECT UNDER THE LAWS OF THE STATE OF MINNESOTA.

PRELIMINARY NOT FOR CONSTRUCTION

EFH Co. General Contractor
2999 W. County Road 42, Suite 206
Burnsville, MN 55306
952-890-6450
952-890-5476 Fax
info@efhco.com

9801 LYNDALE AVENUE S
Bloomington, Minnesota

Copyright 2018 Leonard Lampert Architects Inc.


Project Designer: L. SCHMIDT
Drawn By: LLS
Checked By: LL

| Revisions | 5/1/18 | REVISED |
|-----------|--------|---------|
| | | |
| | | |
| | | |
| | | |
| | | |

FLOOR PLAN DETAILS & CODE REVIEW

Sheet Number

A1



LAMPERT
 ARCHITECTS

420 Summit Avenue
 St. Paul, MN 55102
 Phone: 763.755.1211 Fax: 763.757.2849
 lampert@lampert-arch.com

ARCHITECT CERTIFICATION:
 I HEREBY CERTIFY THAT THIS PLAN,
 SPECIFICATION OR REPORT WAS
 PREPARED BY ME OR UNDER MY DIRECT
 SUPERVISION AND THAT I AM A DULY
 LICENSED ARCHITECT UNDER THE
 LAWS OF THE STATE OF MINNESOTA.

PRELIMINARY
 NOT FOR
 CONSTRUCTION

EFH Co.
 General Contractor
 2999 W. County Road 42, Suite 206
 Burnsville, MN 55306
 952-890-6450
 952-890-5476 Fax
 info@efhco.com

9801 Lyndale Avenue S
 Bloomington, Minnesota

Copyright 2018
 Leonard Lampert Architects Inc.

Project Designer: L. SCHMIDT

Drawn By: LLS

Checked By: LL

Revisions


| NO. | DATE | DESCRIPTION |
|-----|--------|-------------|
| 1 | 5/1/18 | REVISED |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

WALL SECTIONS

Sheet Number

A2

Project No. 140825-3



1 SECTION AT WINDOW
 A2 SCALE: 3/4" = 1'-0"