
PL202200092 PL2022-92



Scale: 1 inch= 30 Ft.

Luminaire Schedule									
Symbol	Qty Label Arrangement Lumens LLF			Description					
1000	3	M3	SINGLE	23000	0.750	LSI GFM-3-250-PSMV-F			
Security Harris	4	V5	BACK-BACK	23000	0.750	LSI GFM-5-250-PSMV-F			
jung 12003	5	Wl	SINGLE	22000	0.750	LSI GBWM-FT-250-PSMH-F			

Calculation Summary							
Label	CalcType	Units	Avg	Max	Min	Avg/Min	Max/Min
Parking	Illuminance	Fc	2.42	19.47	0.20	12.10	97.35
Inner parking	Illuminance	Fc	2.75	19.47	1.07	2.57	18.20
Outer parking	Illuminance	Fc	1.34	3.27	0.20	6.70	16.35
	L	L	L				

APPROVED

By Londell Pease at 10:56 am, Aug 19, 2014

INSPECTIONS REQUIRED

- Prior to the installation, an inspection to verify delivery of the approved lamp, fixture, and pole must be completed.
- Before a Certificate of Occupancy may be issued, a postinstallation inspection by the Issuing Authority must verify compliance with the approved plan depicting the initial footcandles levels.

Individual points may not vary more than 20 percent from the initial light level on the approved plan.

Any deviation below the Code requirements for the plan must be remedied prior to the issuance of a Certificate of Occupancy (See City Code Section 21.307.07)

CALL (952) 563-8920 for an inspection.

Date Comments


Revisions

9056 Penn Ave South LSI Greenbrier MH

These drawings are for conceptual use only and are not intended for construction. Values represented are an approximation generated from manufacturers photometric inhouse or independent lab tests with data supplied by Jamp manufacturers.

Inspected on August 18, 2014 by Dennis Fields. PASSED INSPECTION See inspection noted on plan.

PL202200092 PL2022-92



Scale: 1 inch= 30 Ft.

	Luminaire Schedule									
3	Symbol	Qty	Label	Arrangement	Lumens LLF		Description			
		3	M3	SINGLE	23000	1.000	LSI GFM-3-250-PSMV-F			
	OULD HINT	4	₹5	BACK-BACK	23000	1.000	LSI GFM-5-250-PSMV-F			
	1003	5	Wl	SINGLE	22000	1.000	LSI GBWM-FT-250-PSMH-F			

Calculation Summary							
Label	CalcType	Units	Avg	Max	Min	Avg/Min	Max/Min
Parking	Illuminance	Fc	3.23	25.96	0.26	12.42	99.85
Inner parking	Illuminance	Fc	3.67	25.96	1.43	2.57	18.15
Outer parking	Illuminance	Fc	1.79	4.36	0.26	6.88	16.77

APPROVED

By Londell Pease at 10:57 am, Aug 19, 2014

INSPECTIONS REQUIRED

- 1) Prior to the installation, an inspection to verify delivery of the approved lamp, fixture, and pole must be completed.
- 2) Before a Certificate of Occupancy may be issued, a postinstallation inspection by the Issuing Authority must verify compliance with the approved plan depicting the initial footcandles levels.

Individual points may not vary more than 20 percent from the initial light level on the approved plan.

Any deviation below the Code requirements for the plan must be remedied prior to the issuance of a Certificate of Occupancy (See City Code Section 21 307 07)

CALL (952) 563-8920 for an inspection.

Greenbrier MH Intial

These drawings are for conceptual use only and are not intended for construction. Values represented are an approximation generated from manufacturers photometric inhouse or independent lab tests with data supplied by Jamp manufacturers

Revisions