

12/10/2025 9:58:48 AM C:\rent\Project Files\25-0022_A03_central_sangalli\UGSL.rvt

2 NORTH ELEVATION

A301 1/16" = 1'-0"



60% PRIMARY MATERIALS; 40% SECONDARY MATERIALS

4 NORTH ELEVATION - INSIDE

A301 1/16" = 1'-0"



(NORTH ELEVATION TOTAL) 60% PRIMARY MATERIALS; 40% SECONDARY MATERIALS

3 EAST ELEVATION

A301 1/16" = 1'-0"



36% PRIMARY MATERIALS; 64% SECONDARY MATERIALS

5 SOUTH ELEVATION

A301 1/16" = 1'-0"



44% PRIMARY MATERIALS; 56% SECONDARY MATERIALS

1 WEST ELEVATION - LYNDALE AVE

A301 1/16" = 1'-0"



65% PRIMARY MATERIALS; 35% SECONDARY MATERIALS

GENERAL EXTERIOR NOTES:

-
-

KEYNOTES:

- E01 FIBER CEMENT LAP SIDING, 6" EXPOSURE - COLOR 1
E02 FIBER CEMENT LAP SIDING, 12" EXPOSURE - COLOR 2
E03 FIBER CEMENT LAP SIDING, 4" EXPOSURE - COLOR 3
E04 FIBER CEMENT PANEL - COLOR 3
E05 MASONRY VENEER - NORMAN BRICK 1/2 RUNNING BOND
E06 BURNISHED BLOCK
E14 ALUMINUM FABRICATION - BUILDING CANOPY
E17 ALUMINUM STOREFRONT SYSTEM - POWDER COATED BLACK - CENTER SET
E20 PREFINISHED METAL OVERHEAD GARAGE DOOR - COLOR TBD
E21 COMPOSITE WINDOW SYSTEM
E22 INTERNALLY LIT, CHANNEL LETTER BUILDING SIGNAGE
E29 ROOFTOP EQUIPMENT SCREENING

EXTERIOR MATERIALS:

- MASONRY BRICK VENEER
COLOR: TBD
MANUFACTURER: TBD
SIZE: NORMAN
BOND: HALF RUNNING
PRIMEX VENT COLOR: SELECTION by ARCHITECT
- FIBER CEMENT 6" SIDING
COLOR: TBD
MANUFACTURER: TBD
EXPOSURE: 6"
PRIMEX VENT COLOR: SELECTION by ARCHITECT
- FIBER CEMENT 12" SIDING
COLOR: TBD
MANUFACTURER: TBD
EXPOSURE: 6"
PRIMEX VENT COLOR: SELECTION by ARCHITECT
- FIBER CEMENT 4" SIDING
COLOR: TBD
MANUFACTURER: TBD
EXPOSURE: 4"
PRIMEX VENT COLOR: SELECTION by ARCHITECT
- FIBER CEMENT PANEL SIDING
COLOR: TBD
MANUFACTURER: TBD
PRIMEX VENT COLOR: SELECTION by ARCHITECT

12/10/2025 9:58:54 AM C:\rent\Project Files\25-0022_A302_central_sangalli\UGSLJ.rvt

1 COURTYARD NORTH ELEVATION
A302 1/16" = 1'-0"



36% PRIMARY MATERIALS; 64% SECONDARY MATERIALS

2 COURTYARD SOUTH ELEVATION
A302 1/16" = 1'-0"



33% PRIMARY MATERIALS; 67% SECONDARY MATERIALS

3 COURTYARD WEST ELEVATION
A302 1/16" = 1'-0"



56% PRIMARY MATERIALS; 44% SECONDARY MATERIALS

4 COURTYARD EAST ELEVATION
A302 1/16" = 1'-0"

42% PRIMARY MATERIALS; 58% SECONDARY MATERIALS

GENERAL EXTERIOR NOTES:

-
-

KEYNOTES:

- | | |
|-----|---|
| E01 | FIBER CEMENT LAP SIDING, 6" EXPOSURE - COLOR 1 |
| E02 | FIBER CEMENT LAP SIDING, 12" EXPOSURE - COLOR 2 |
| E03 | FIBER CEMENT LAP SIDING, 4" EXPOSURE - COLOR 3 |
| E05 | MASONRY VENEER - NORMAN BRICK 1/2 RUNNING BOND |
| E14 | ALUMINUM FABRICATION - BUILDING CANOPY |
| E17 | ALUMINUM STOREFRONT SYSTEM - POWDER COATED BLACK - CENTER SET |
| E21 | COMPOSITE WINDOW SYSTEM |
| E29 | ROOFTOP EQUIPMENT SCREENING |

EXTERIOR MATERIALS:

- | | |
|--|--|
| | MASONRY BRICK VENEER
COLOR: TBD
MANUFACTURER: TBD
SIZE: NORMAN
BOND: HALF RUNNING
PRIMEX VENT COLOR: SELECTION by ARCHITECT |
| | FIBER CEMENT 6" SIDING
COLOR: TBD
MANUFACTURER: TBD
EXPOSURE: 6"
PRIMEX VENT COLOR: SELECTION by ARCHITECT |
| | FIBER CEMENT 6" SIDING
COLOR: TBD
MANUFACTURER: TBD
EXPOSURE: 6"
PRIMEX VENT COLOR: SELECTION by ARCHITECT |
| | FIBER CEMENT PANEL SIDING
COLOR: TBD
MANUFACTURER: TBD
PRIMEX VENT COLOR: SELECTION by ARCHITECT |